

**Name of the Work "Grade-II Metalling with Culvert from Butipada to Gochhara**

**TENDER SCHEDULE**

SI NO	Description of Item	Unit	Quantity	Rate	Amount
1	Earth work excavation in hard soil within initial lead and lift of 50m and 1.5m including rough dressing and leveling the bed & depositing the soil away from working area etc complete.	cum	39.17	197.60	7740.00
2	Filling in foundation and plinth with sand, watered and rammed including cost, conveyance & royalty of materials.	cum	5.71	325.13	1855.00
3	Cement Concrete in (1:3:6) using 40mm. Size H.G. metal including laying compacting, Curing with cost, carriage and royalty etc. complete	cum	45.87	5092.85	233609.00
4	R.C.C. M-20 Grade With 20mm and down Grade C.B. Chips of approved quality from approved quarry including hoisting, laying hire charges of concrete mixture, vibrator watering, curing and cost of all materials and labour, T & P etc Complete but excluding cost of reinforcement complete.	cum	4.50	5322.65	23952.00
5	C.C. (1:2:4) using 12mm size H.G. hand broken chips for wearing coat including cost, conveyance, Royalty etc. complete.	cum	0.59	6498.64	3834.00
6	Labour for straightening , Cutting, bending & binding the M.S. Road including cost of binding wire and cost of MS Road	Qtnl	4.500	9087.49	40894.00
7	Rigid and smooth centering and shuttering for R.C.C. work and dismantling then after casting including cost of all materials complete				
	(A) Mass Concrete	Sqm	27.600	113.05	3120.00
	(B) Roof slab & Chajja	Sqm	9.000	445.38	4008.00
8	Earth work excavation hard soil with initial lead of 50m and initial lift of 1.5m including breaking the colds to max 5 to 7 cm size and laying in layers not more than 30 cm etc complete.	cum	337.50	164.67	55576.00
9	Collection, conveyance, stacking of good laterite moorum to road sid with box heaps of 1.5m*1Collection, conveyance, stacking of good laterite moorum to road sid with box heaps of 1.5m*1.5*.5 to be measured as 1 cum.	cum	842.81	279.71	235740.00

	Collection, conveyance, stacking of 63 mm to 40 mm size H.G.metal to road side with box heaps of 1.5 x1.5 x 0.5m to be measured as 1 cum.	cum	273.75	1484.56	406398.00
11	Coveying from stacks and spreading Morrum on sub-base, watering and compacting with PRR including hire and running charges of PRR etc. Coveying from stacks and spreading Morrum on sub-base, watering and compacting with PRR	cum	705.94	344.68	243320.00
12	Coveying from stacks and spreading over size metal of size 50 mm to 40mm hard stone metal for metaling packing to voids with small stone and hand packing the same to proper camber conveying from stacks & watering turf edging etc. and consolidation with PRR including hire and running charges of PRR etc.	cum	273.75	605.84	165849.00
13	Provision for Transparency Board				3000.00
					1428895.00
14	Add 1% for labour Cess				14289.00
					1443184.00
15	Add GST 18%				257201.00
					1700385.00
				Limited to	<b>1700000.00</b>

**The Tenderer are required to put their percentage of rate in the blank space given below, failing which the tender document will be rejected.**

**My/Our quoted rate is \_\_\_\_\_%(Figure) \_\_\_\_\_ (In words)**

**\*Less than/Excess over/ Equal to the amount put to tender.**

Total number of Items:.....	
Number of Corrections:.....	
Number of interpolation:.....	
Number of over writings:.....	
E.M.D Funnished/EMD Exempted	
(A)Demand Draft No.....	
(B)Ammount Rs.....	
Copy of PAN card:furnished/not furnished	
Copy of GST Registration:furnished/not furnished	
Copy of Contractor's Licecence:furnished/not furnished	
Copy of Experience certificate:furnished/not furnished	
Total No of sheets in the Tender Papers:.....	

**Full Signature of Contractor**

**Signature of the Bidder/Tenderer**

  
**Signature of the B.D.O  
Kuchinda**