

| TENDER SCHEDULE FOR COMPLETION OF KALYAN MANDAP AT PARMANPUR | | | | | |
|--|---|----------|----------|----------|-------------------|
| SI No | Item | Quantity | Unit | Rate | Amount |
| 01 | Earth work in excavation in foundation on hard soil within initial lead & lift including rough dressing breaking the clods & laying in layers not exceeding 0.30m depth | 5.95 | One Cum | 206.77 | 1230.28 |
| 02 | Filling of foundation with sand & well water & rammed etc. complete including royalty. | 60.38 | One Cum | 512.72 | 30958.00 |
| 03 | C.C. (1:3:6) using 4cm CBHG metal including cost conveyance & roalty etc. Complete. | 31.37 | One Cum | 5181.70 | 162550.00 |
| 04 | C.C. (1:2:4) using 12mm CBHG chips including cost conveyance & roalty etc. Complete. | 4.18 | One Cum | 6683.25 | 27936.00 |
| 5 | R.C.C.M20 grade with using 20mm down grade hard granite C.B. Chips including Cost, Conveyance and royalty etc complete. | 35.65 | One Cum | 5447.10 | 194189.00 |
| 6 | Supplying, fitting & placing uncoated HYSD bar reinforcement complete as per drawing and technical specification. | 35.65 | One Qntl | 8954.91 | 319242.00 |
| 7 | Rigid smooth centering and shuttering for RCC works including false works & dismantling then after casting etc. | | | | |
| | Lintel Band | 19.28 | One Sqm | 283.56 | 5467.00 |
| | Wall beam & Room beam | 69.57 | One Sqm | 788.00 | 54821.00 |
| | Slab & Chhaja | 221.01 | One Sqm | 459.40 | 101532.00 |
| 8 | Brick work with Fly ash bricks in (1:6) S/S | 12.24 | One Cum | 4595.02 | 56243.00 |
| 9 | 12mm thick cement plastering with C.M. (1:6) on over the brick work with cost conveyance & royalty etc complete . | 210.48 | One Sqm | 155.70 | 32772.00 |
| 10 | 16mm thick cement plastering with C.M. (1:6) on over the brick work with cost conveyance & royalty etc complete . | 240.34 | One Sqm | 221.30 | 53187.00 |
| 11 | 6 mm thick cement plastering with C.M. (1:4) on over the RCC Surface | 238.29 | One Sqm | 170.20 | 40557.00 |
| 12 | Fixing tiles in floors,treads or steps and landings on 25 mm thick CM (1:1) jointed with neat cement slurry mixed with pigments to match the shades includind cost of vetrified tiles | 231.66 | One Sqm | 1129.20 | 261590.00 |
| 13 | Supplying,fitting & fixing of MS door and windows | 824.68 | Kg | 111.70 | 92116.00 |
| 14 | Paintig two coat with any approved synthetic enamel paint | 38.06 | One Sqm | 182.70 | 6953.00 |
| 15 | Finishing walls with acrylic wall puty(cement based) of approved make and finished smooth and even surface. | 478.63 | One Sqm | 139.70 | 66865.00 |
| 16 | Wall priming one coat with wall primer of approved shade to give an even shade including cost of Primer. | 689.11 | One Sqm | 64.30 | 44310.00 |
| 17 | Paintig two coats over a coat of primer with Plastic emulsion paint of approved shade on new work to give an even shade including cost of paint. | 478.63 | One Sqm | 84.40 | 40396.00 |
| 18 | Finishing walls with water proofing weather coat paint of approved make and finished smooth and even surface. | 210.48 | One Sqm | 80.50 | 16944.00 |
| 19 | Supplying,fitting & fixing of Aluminium Sliding Window | | | | 80000.00 |
| | | | | Total Rs | 1689858.28 |

My / our quoted rate is _____ % (both in figure and words) excess over / less than / equal to the above estimated cost.

Signature of Bidder

BDO, Maneswar

NOTES:

1. The contractor should not write any thing excepting quoting of percentage and in case anything else regarding tender rate is mentioned, it
2. Strike out which is not applicable.
3. Percentage should be quoted up to 2 (Two) digits after the decimal point.
4. Rate of all items are inclusive of cost, carriage, royalty and other taxes of material.

Tenderer

No. of Correction:

No. of over writing:

No. of interpolation:

ne tender is liable for