

BILL OF QUANTITY (Const. of Cow Shelter / Shed at Shree Krishna Goshala,Potapali,Sambalpur)

SI. No.	Item of Work	Quantity to be executed	Unit	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation in foundation in hard with initial leads and lifts including dressing and leveling the bed and depositing the excavated earth at places away from work site with all leads and lifts including cost of all labour and T&P and dewatering if required for the work etc. complete	213.50	Cum	270.90	57,836.00
2	Filling foundation and plinth with sand well watered & rammed with cost, conveyance,royalty,taxes etc. complete.	357.85	Cum	704.68	2,52,169.00
3	Filling foundation and plinth with excavated materials and well watered & rammed with cost, conveyance,royalty,taxes etc. complete.	142.33	Cum	151.25	21,527.00
4	Cement concrete(1:3:6) with 4cm size hard granite metal including cost, conveyance, royalty, taxes, watering and curing etc. complete.	140.71	Cum	5715.60	8,04,269.00
5	Brick work with Fly Ash. bricks in F&P having crusing strength between 75kg/cm2 in cement motar (1:6) with cost, coveyance, royalty watering & curing etc. complete.	77.59	Qntl	5540.30	4,29,885.00
6	R.C.C. work of M-20 Grade with 20mm and down graded b.h.c.b.g. chips including hoisting and laying.				0.00
A	i)Column base	82.57	Sqm	6276.42	5,18,214.00
B	ii)Plinth Beam	19.46	Sqm	7142.71	1,38,970.00
C	iii) Column in Superstructure	23.77	Sqm	15419.44	3,66,551.00
D	iv) Lintel	13.15	Sqm	13889.45	1,82,700.00
7	Supplying ,fitting and placing uncoated HYSD bar reinforcement complete as per drawing and technical specification.	177.51	Sqm	8946.95	15,88,138.00
8	Cementconcrete(1:2:4) with 12mm size hard granite chips including cost, conveyance, royalty, taxes, watering and curing etc. complete.	120.56	Sqm	7365.40	8,87,958.00
9	Flyash Brick masonry C. M. (1:6)in superstructure with splay cutting circular moulding etc including cost, conveyance of all material and labour etc complete as per the direction of EIC.	58.47	Sqm	5578.28	3,26,139.00
10	12mm thick cement plaster (1:6) over brick work with cst of all materials and all labour etc.	407.35		186.20	75,849.00
11	16mm thick cement plaster (1:6) over brick work with cst of all materials and all labour etc.	278.71	Cum	268.70	74,891.00
12	Supplying, fitting & fixing of MS shutter of approved design made out of MS angle and sheet of approved specification including cost conveyance of all material etc complete as per the direaction of EIC	174.19	Cum	104.80	18,255.00
13	Supplying, fabrication, fitting, fixing & errection of MS tubular Truss & purline including all cost & convaynce of materials etc. Complete.	62.65	Cum	6485.90	4,06,342.00
14	Manufacturing, Supplying (50mmx100mmx50mm) 5mm thick C-Chanel, purlin, runner and fender to plinth band (Angular) including fabrication, fitting, fixing in position including all cost & convaynce of materials etc. Complete.	52.58	Sqm	6485.90	3,41,016.00
15	Painting 2coats over a coat of primer including cost of paints, labour& sundries etc complete	1046.80	Sqm	265.10	2,77,507.00

Sl. No.	Item of Work	Quantity to be executed	Unit	Rate	Amount
1	2	3	4	5	6
16	Supplying fitting & fixing of anticorrosive zinc aluminium alloy painted cloured steel roofing Profile sheet of 1000mm width & total coated thickness 0.40mm in roof including fixing of ridge cap with fasteners of approved specifications etc complete but excluding cost of fasteners including drilling hole in wind ties including fixing of ridges valleys, wind ties etc. complete including cost of sheet & all fitting (per 1 Sq. Mtr.)	836.10	Sqm	1000.40	8,36,434.00
17	Supplying, fitting & fixing of holding down bolts (600mmx20mm) & base plates of 8mm thickness including all cost & conveyance of materials etc. Complete.	422.00	Sqm	97.80	41,272.00
18	Finishing walls with two coats of water proofing cement paint of approved shade on new work to give an even shade.	548.56	Sqm	44.30	24,301.00
19	Wall painting 2 coats with weather coat of approved shade on old work to give an even shade.	251.28	Sqm	101.80	25,580.00
				GRAND TOTAL	76,95,803.00

(RUPEES SEVENTY SIX LAKHS NINETY FIVE THOUSAND EIGHT HUNDRED THREE) ONLY

APPROVED FOR 19 (NINETEEN) ITEMS ONLY

Rajniw
 Addl. Executive Officer (Tech)
 Zilla Parishad, Sambalpur

My/our quoted rate is % (both in figures and words) excess over

Signature of Tenderer

NOTES :-

1. The contractor should not write anything excepting quoting of percentage and in any case anything else regarding tender rate
2. Percentage quoted by the tenderer shall be accurately filled in words and in figures..
3. Strike out which is not applicable. If the tenderer quotes the percentage without mentioning excess or less, it will be
4. Percentage should be quoted up to (one) digit after the decimal point. If the tenderer writes more than 1 digit after decimal,
5. Rate of all items are inclusive of cost, carriage, royalty, cess and other taxes of materials.

Tenderer

No. of corrections.....
 No. of Over writings.....
 No. of Interpolations.....

Contractor

[Signature]
 Block Development Officer
 Dhankauda